Southern Cumberland Plateau Regional Water Supply Planning


Pilot Study

27 August 2010

Benjamin L. Rohrbach, P.E. Chief, Hydrology and Hydraulics U.S. Army Corps of Engineers Nashville District



US Army Corps of Engineers
BUILDING STRONG®



Presentation Outline

- Project Update Overview
- Water Demand Projections
- Existing Source Yield Estimates
- Regional Need Statements
- Alternatives Under Consideration
- OASIS Modeling of Source/Systems Reliability
- Alternative Screening Protocol and Decision Matrix



Project Update Overview

Complete:

- ▶ Water Demand Projections
- ► Existing Water Source Yield Analyses
- ► Alternative Water Source Identification
- ► Preliminary Design/Yield of Alternative Water Sources
- ▶ Preliminary Cost Estimates

Underway:

- ► Final Design/Yield of Alternative Water Sources
- ▶ Final Cost Estimates
- Alternative Screening Matrix



Demand Projections

- Driven by Population Growth
 - ▶ Projections from UT Center for Business and Economic Research (CBER)
 - ▶ Growth in system population served in direct proportion to CBER growth estimates
- Commercial and Industrial Use
 - ► Proportional to population growth and density
 - Statewide evaluation of ratio of commercial/industrial to residential water use
 - ▶ Increases to 1:1 ratio at 1000 persons/sq. mile



Demand Projections


| Utility | 2005 | 2010 | 2020 | 2030 |
|----------------|------|------|------|------|
| Sewanee* | .294 | .303 | .330 | .349 |
| Monteagle* | .433 | .434 | .431 | .434 |
| Tracy City* | .470 | .471 | .467 | .471 |
| Big Creek* | .867 | .881 | .910 | .940 |
| Griffith Creek | .079 | .079 | .078 | .078 |
| Foster Falls | .034 | .034 | .034 | .034 |
| Cagle-Fredonia | .129 | .141 | .177 | .201 |

^{*} Average Daily Raw Water Withdrawals



Sewanee, TN


- Current Sewanee average demand is .303 MGD
- ➤ The combined firm yield of multiple sources is estimated as .498 MGD
- Sewanee UD
 possesses adequate
 source water and
 treatment capacity
- Wastewater discharge limiting factor





Monteagle, TN


- Current Monteagle average demand is .434 MGD
- ► The firm yield of primary and secondary sources estimated as .468 MGD
- Projected demand through the study period is nearly constant
- Monteagle impacted most dramatically during recent drought





Tracy City, TN


- Current Tracy City average demand is .471 MGD
- The firm yield of Big Fiery Gizzard lake estimated as .347 MGD
- .65 MGD average release required by permit for minimum flow downstream





Big Creek Utility District


- Current Big Creek
 Utility District average
 demand is .881 MGD
- ► The firm yield of Ranger Lake estimated as 1.093 MGD
- Big Creek UD
 possesses adequate
 source water and
 treatment capacity





Southern Cumberland Plateau Region

- Existing average demand for the region is 2.343 MGD, projected to reach 2.507 MGD by 2030
- ► The combined firm yield of existing sources in the region has been estimated as 2.406 MGD
- As a region, there is a demonstrated need for additional water





Regional Need Statements Southern Cumberland Plateau Pilot Area

- The current raw water supply in the region was perceived as barely sufficient during the recent drought. The hardest hit utility, Monteagle, managed the drought by purchasing finished water through connections to Sewanee and Tracy City, and by establishing several emergency raw water sources.
- Overall raw water demand in the region is expected to grow only slightly, from approximately 2.3 MGD to 2.5 MGD, by the year 2030. The composite firm yield of the region's raw water sources is barely sufficient to meet existing demand, indicating a need for additional source development.
- Interconnections between the utilities are well established, with existing formal contracts between Tracy City and Big Creek, as well as Tracy City and Monteagle. The utilities must maintain and improve this ability to share water among themselves. This is paramount to the region's ability to meet demand during droughts, as the small drainage areas of the South Cumberland Plateau's water sources leaves them particularly vulnerable.

Alternatives Under Consideration

Southern Cumberland Plateau Pilot Area

- Optimizing Water Sharing between Utilities
- Evaluation Utilizes OASIS
 - Existing Interconnections
 - Improved Interconnections

| | | | Contract Information | | | | | | Rates Flow Record | | cord | |
|----------|--------|-----------------|----------------------|---------|----------------|----------|----|--------------|---------------------------|--|---------------|--------------|
| | | | Max (gal p | oer | | Min | | | | | | Max gpd (avg |
| Contract | Seller | Buyer | month) | | Max flow (gpd) | Pressure | D | Date Enacted | Expires | Rates (\$/kgal) | Maximum Month | dayx1.25) |
| Yes | BCUD | TCPU | | 3000000 | | | 50 | 9/21/2009 | 1 yr after first delivery | \$4.0 | 3,165,000 | 105,500 |
| No | SUD | Monteagl | e | | | | | | | | 951,000 | 126,600 |
| | | | | | | | | | | \$1.19 (with > 5 days notice) | | |
| Yes | TCPU | Monteagl | | 1750000 | 250000 | | | 9/20/1999 | | \$2.70 (< 5 days notice & use > 50 kgpd) | 6,054,000 | 235,000 |
| No | TCPU | BCUD | | | | | | Ta | | | 34,546,400 | 1,341,600 |



Alternatives Under Consideration

Southern Cumberland Plateau Pilot Area

New Reservoir on Big Creek

- Earthen Embankment Dam
- Preliminary Expected Project Yield 6.11 MGD
- Total Source Firm Yield 7.43 MGD
- Expected Release Requirement :
 - 2.05 cfs (@ .1 cfsm)
 - 1.32 MGD

Purchase of Ramsey Lake

- Convert Existing Lake to Water Supply Source
- Preliminary Expected Project Yield .58 MGD
- Total Source Firm Yield .67 MGD
- Expected Release Requirement :
 - .14 cfs (@ .1 cfsm)
 - .09 MGD




Alternatives Under Consideration

Southern Cumberland Plateau Pilot Area

- Raise Big Fiery Gizzard Lake
 - Existing Dam Raised 7 feet
 - Preliminary Expected Yield after Project .64 MGD
 - Total Source Firm Yield 1.28 MGD
 - Expected Release Requirement :
 - 1.0 cfs minimum by Permit (.65 MGD)
 - With 2.2 square mile watershed @ .1 cfsm .2 cfs = .13 MGD
- Pipeline to Watts Bar Lake (South Pittsburgh)
 - 220,000 feet of transmission line to Monteagle In 3 Phases
 - Preliminary Expected Project Yield
 - .6 MGD Phase I
 - 3.0 MGD Phase II
 - Extend Services Phase III



OASIS Modeling of Source Reliability





Alternative Screening Protocol

Tier 1:

- ▶ Reliable Capacity
 - Need met with minimal risk
- ▶ Project Cost
 - Feasibility, Design, Construction
- Implementability
 - Permitting, Public Acceptance, Property Acquisitions, Constructability
- ▶ Flexibility
 - Phased Implementation, Drought Resistance



Alternative Screening Protocol

- Tier 2:
 - ▶ Cost
 - Estimated End User Costs
 - Water Quality
 - Raw and Finished
 - Environmental
 - Benefits and Impacts
 - ▶ Multiple Purposes
 - Recreation, etc...
 - ▶ Other Factors



Tier 1 Evaluation Matrix

| Alternative | Reliable Capacity | Cost | Implementability | Flexibility |
|------------------------------|----------------------|--------|------------------|-------------|
| Water Sharing | - | \$ | + | + |
| Reservoir on Big Creek | ++ | \$\$\$ | - | - |
| Raise Big Fiery Gizzard Lake | - | \$ | + | - |
| Purchase Ramsey Lake | + | \$\$ | +/- | - |
| Big Fiery Raise + Ramsey | + | \$\$ | + | + |
| Pipeline to S. Pittsburgh | + | \$\$\$ | - | +/- |

- Based Upon the Tier 1 Qualitative Evaluation, Purchasing Ramsey Lake or a Combination of Raising Big Fiery
 Gizzard and Purchasing Ramsey Lake Appear to be the Preferred Alternative for the Region
- Tier 2 Evaluation Warranted



Questions??

