Sector O - Stormwater Discharges Associated With Industrial Activity From Steam Electric Power Generating Facilities, Including Coal Handling Areas

1. Discharges Covered Under This Section

The requirements listed under this section shall apply to stormwater discharges from steam electric power generating facilities, including coal handling areas. Non-stormwater discharges subject to effluent limitations guidelines are not covered by this permit. Storm water discharges from coal pile runoff subject to numeric limitations are eligible for coverage under this permit, but are subject to the limitations established by 40 CFR 423.

SIC	Sector O: Steam Electric Power Generating Facilities	Sampling	Table
Code		Required?	Number
4911	Electric Services	Yes	O-1& 2

When an industrial facility, described by the above coverage provisions of this section, has industrial activities being conducted onsite that meet the description(s) of industrial activities in another section(s), that industrial facility shall comply with any and all applicable monitoring and pollution prevention plan requirements of the other section(s) in addition to all applicable requirements in this section. The monitoring and pollution prevention plan terms and conditions of this multi-sector permit are additive for industrial activities being conducted at the same industrial facility (co-located industrial activities). The operator of the facility shall determine which other monitoring and pollution prevention plan section(s) of this permit (if any) are applicable to the facility.

Limitations on Coverage. Storm water discharges from ancillary facilities such as fleet centers, gas turbine stations, and substations that are not contiguous to a steam electric power generating facility are not covered by this permit. Heat capture co-generation facilities are not covered by this permit; however, dual fuel co-generation facilities are included.

2. Special Conditions

Prohibition of Non-stormwater Discharges. Except for those allowable non-stormwater discharges included in Part 3.1.2 (Allowable Non-Stormwater Discharges) of this permit, there are no other non-stormwater discharges authorized in this Sector.

3. Stormwater Pollution Prevention Plan Requirements

- 3.1 Deadlines for Plan Preparation and Compliance. There are no additional deadlines for plan preparation and compliance, other than those stated in subpart 4.1.
- 3.2 Contents of Plan. The plan shall include, at a minimum, the following items:
- 3.2.1 Pollution Prevention Team. Each plan shall identify a specific individual or individuals within the facility organization as members of a stormwater Pollution Prevention Team that are responsible for developing the stormwater pollution prevention plan and assisting the facility or plant manager in its implementation, maintenance, and revision. The plan shall

clearly identify the responsibilities of each team member. The activities and responsibilities of the team shall address all aspects of the facility's stormwater pollution prevention plan.

- 3.2.2 Description of Potential Pollutant Sources. Each plan shall provide a description of potential sources which may reasonably be expected to add significant amounts of pollutants to stormwater discharges or which may result in the discharge of pollutants during dry weather from separate storm sewers draining the facility. Each plan shall identify all activities and significant materials which may potentially be significant pollutant sources. Each plan shall include, at a minimum:
- 3.2.2.1 Drainage. A site map which clearly outlines the locations of the following, as they apply to the facility: The outfall locations and the types of discharges contained in the drainage areas of the outfalls, and an outline of the drainage area of each stormwater outfall that is within the facility boundaries (and indicating the direction of stormwater flow); processing areas and buildings; treatment ponds; locations where significant materials are exposed to precipitation; storage tanks; scrap yards, and general refuse areas; fuel storage and distribution areas; vehicle and equipment maintenance and storage areas; loading/unloading areas; locations used for treatment, storage or disposal of wastes; location of short and long term storage of general materials (including but not limited to: supplies, construction materials, plant equipment, oils, fuels, used and unused solvents, cleaning materials, paint, water treatment chemicals, fertilizers, and pesticides); landfills; location of construction sites; locations of stock pile areas (such as coal piles and limestone piles); locations where major spills or leaks identified under Spills and Leaks subpart of this permit have occurred; surface water bodies; and existing structural control measures to reduce pollutants in stormwater runoff (such as bermed areas, grassy swales, etc.).

For each stormwater outfall identify the types of pollutants which are likely to be present in the stormwater discharges. Factors to consider include the toxicity of a chemical; quantity of chemicals used, produced or discharged; the likelihood of contact with stormwater; and history of significant leaks or spills of toxic or hazardous pollutants. Flows with a significant potential for causing erosion shall be identified.

- 3.2.2.2 Inventory of Exposed Materials An inventory of the types of materials handled at the site that potentially may be exposed to precipitation. Such inventory shall include a narrative description of significant materials that have been handled, treated, stored or disposed in a manner to allow exposure to stormwater between the time of 3 years prior to the date of the submission of an NOI to be covered under this permit and the present; method and location of onsite storage or disposal; materials management practices employed to minimize contact of materials with stormwater runoff between the time of 3 years prior to the date of the submission of an NOI to be covered under this permit and the present; the location and a description of existing structural and nonstructural control measures to reduce pollutants in stormwater runoff; and a description of any treatment the stormwater receives.
- 3.2.2.3 Spills and Leaks A list of significant spills and significant leaks of toxic or hazardous pollutants that occurred at areas that are exposed to precipitation or that otherwise drain to a stormwater conveyance at the facility after the date of 3 years prior to the date of the submission of an NOI to be covered under this permit. Such list shall be updated as appropriate during the term of the permit.

- 3.2.2.4 Sampling Data A summary of existing discharge sampling data describing pollutants in stormwater discharges from the facility, including a summary of sampling data collected during the term of this permit.
- 3.2.2.5 Risk Identification and Summary of Potential Pollutant Sources A narrative description of the potential pollutant sources from the following activities: loading and unloading operations; outdoor storage activities; outdoor manufacturing or processing activities; significant dust or particulate generating processes; and onsite waste disposal practices. The description shall specifically list any significant potential source of pollutants at the site and for each potential source, any pollutant or pollutant parameter (e.g., total suspended solids, copper, etc.) of concern shall be identified.
- 3.2.3 Measures and Controls. Each facility covered by this permit shall develop a description of stormwater management controls appropriate for the facility, and implement such controls. The appropriateness and priorities of controls in a plan shall reflect identified potential sources of pollutants at the facility. The description of stormwater management controls shall address the following minimum components, including a schedule for implementing such controls:
- 3.2.3.1 Good Housekeeping Good housekeeping requires the maintenance of areas which may contribute pollutants to stormwater discharges in a clean, orderly manner. The following areas must be specifically addressed:
- 3.2.3.1.1 Fugitive Dust Emissions The plan must describe measures that prevent or minimize fugitive dust emissions from coal handling areas. The permittee shall consider establishing procedures to minimize offsite tracking of coal dust. To prevent offsite tracking the facility may consider specially designed tires, or washing vehicles in a designated area before they leave the site, and controlling the wash water.
- 3.2.3.1.2 Delivery Vehicles The plan must describe measures that prevent or minimize contamination of stormwater runoff from delivery vehicles arriving on the plant site. At a minimum the permittee should consider the following:
 - Develop procedures for the inspection of delivery vehicles arriving on the plant site, and ensure overall integrity of the body or container; and
 - Develop procedures to deal with leakage or spillage from vehicles or containers, and ensure that proper protective measures are available for personnel and environment.
 - Fuel Oil Unloading Areas The plan must describe measures that prevent or minimize contamination of stormwater runoff from fuel oil unloading areas. At a minimum the facility operator must consider using the following measures, or an equivalent:
 - Use containment curbs in unloading areas;
 - During deliveries station personnel familiar with spill prevention and response procedures must be present to ensure that any leaks or spills are immediately contained and cleaned up; and

Sector O

- Use spill and overflow protection (drip pans, drip diapers, and/or other containment devices shall be placed beneath fuel oil connectors to contain any spillage that may occur during deliveries or due to leaks at such connectors).
- 3.2.3.1.3 Chemical Loading/Unloading Areas The plan must describe measures that prevent or minimize the contamination of stormwater runoff from chemical loading/unloading areas. The areas surrounding storm drain inlets and outfall points should also be free of material that could discharge off-site and contribute to pollutants in stormwater. Where practicable, chemical loading/unloading areas should be covered, and chemicals should be stored indoors.

At a minimum the permittee must consider using the following measures or an equivalent:

- Use containment curbs at chemical loading/unloading areas to contain spills; and
- During deliveries station personnel familiar with spill prevention and response procedures must be present to ensure that any leaks or spills are immediately contained and cleaned up.
- 3.2.3.1.4 Miscellaneous Loading/Unloading Areas The plan must describe measures that prevent or minimizes the contamination of stormwater runoff from loading and unloading areas. The facility may consider covering the loading area, minimizing stormwater run-on to the loading area by grading, berming, or curbing the area around the loading area to direct stormwater away from the area, or locate the loading/unloading equipment and vehicles so that leaks can be contained in existing containment and flow diversion systems.
- 3.2.3.1.5 Liquid Storage Tanks The plan must describe measures that prevent or minimize contamination of stormwater runoff from above ground liquid storage tanks. At a minimum the facility operator must consider employing the following measures or an equivalent:
 - Use protective guards around tanks;
 - Use containment curbs;
 - Use spill and overflow protection (drip pans, drip diapers, and/or other containment devices shall be placed beneath chemical connectors to contain any spillage that may occur during deliveries or due to leaks at such connectors); and
 - Use dry cleanup methods.
 - Large Bulk Fuel Storage Tanks The plan must describe measures that prevent or minimize contamination of stormwater runoff from liquid storage tanks. At a minimum the facility operator must consider employing the following measures, or an equivalent:
 - Comply with applicable State and Federal laws, including Spill Prevention Control and Countermeasures (SPCC); and
 - Containment berms.
- 3.2.3.1.6 The plan must describe measures to reduce the potential for an oil spill, or a chemical spill, or reference the appropriate section of their SPCC plan. At a minimum the structural integrity of all above ground tanks, pipelines, pumps and other related equipment shall be visually inspected on a weekly basis. All repairs deemed necessary based on the findings of the inspections shall be completed immediately to reduce the incidence of spills and leaks occurring from such faulty equipment.

- 3.2.3.1.7 Oil Bearing Equipment in Switchyards The plan must describe measures to reduce the potential for stormwater contamination from oil bearing equipment in switchyard areas. The facility operator may consider level grades and gravel surfaces to retard flows and limit the spread of spills; collection of stormwater runoff in perimeter ditches.
- 3.2.3.1.8 Residue Hauling Vehicles All residue hauling vehicles shall be inspected for proper covering over the load, adequate gate sealing and overall integrity of the body or container. Vehicles without load coverings or adequate gate sealing, or with leaking containers or beds must be repaired as soon as practicable.
- 3.2.3.1.9 Ash Loading Areas Plant procedures shall be established to reduce and/or control the tracking of ash or residue from ash loading areas including, where practicable, requirements to clear the ash building floor and immediately adjacent roadways of spillage, debris and excess water before each loaded vehicle departs.
- 3.2.3.1.10 Areas Adjacent to Disposal Ponds or Landfills The plan must describe measures that prevent or minimize contamination of stormwater runoff from areas adjacent to disposal ponds or landfills. The facility must develop procedures to:
 - Reduce ash residue which may be tracked on to access roads traveled by residue trucks or residue handling vehicles; and
 - Reduce ash residue on exit roads leading into and out of residue handling areas.
- 3.2.3.1.11 Landfills, Scrapyards, Surface Impoundments, Open Dumps, General Refuse Sites The plan must address landfills, scrapyards, surface impoundments, open dumps and general refuse sites. The permittee is referred to Parts 11.L. and 11.N of the permit for applicable Best Management Practices (BMPs).
- 3.2.3.1.12 Maintenance Activities For vehicle maintenance activities performed on the plant site, the permittee shall use the applicable BMPs outlined in Part 11.P. of the permit (Stormwater Discharges Associated With Industrial Activity From Motor Freight Transportation Facilities, Passenger Transportation Facilities, Rail Transportation Facilities, and United States Postal Service Transportation Facilities).
- 3.2.3.1.13 Material Storage Areas The plan must describe measures that prevent or minimize contamination of stormwater from material storage areas (including areas used for temporary storage of miscellaneous products, and construction materials stored in lay down areas). The facility operator may consider flat yard grades, runoff collection in graded swales or ditches, erosion protection measures at steep outfall sites (e.g., concrete chutes, riprap, stilling basins), covering lay down areas, storing the materials indoors, covering the material with a temporary covering made of polyethylene, polyurethane, polypropylene, or hypalon. Storm water run-on may be minimized by constructing an enclosure or building a berm around the area.
- 3.2.3.2 Preventive Maintenance A preventive maintenance program shall be implemented and shall include timely inspection and maintenance of stormwater management devices (e.g., cleaning oil/water separators, catch basins) as well as inspecting and testing facility equipment and

systems to uncover conditions that could cause breakdowns or failures resulting in discharges of pollutants to surface waters, and ensuring appropriate maintenance of such equipment and systems.

- 3.2.3.3 Spill Prevention and Response Procedures Areas where potential spills which can contribute pollutants to stormwater discharges can occur, and their accompanying drainage points, shall be identified clearly in the stormwater pollution prevention plan. The plan should be consider specifying material handling procedures, storage requirements, and use of equipment such as diversion valves. Procedures for cleaning up spills shall be identified in the plan and made available to the appropriate personnel. The necessary equipment to implement a clean-up should be available to personnel.
- 3.2.3.4 Inspections In addition to or as part of the comprehensive site evaluation required under this section, qualified facility personnel shall be identified to inspect the following areas on a monthly basis: coal handling areas, loading/unloading areas, switchyards, fueling areas, bulk storage areas, ash handling areas, areas adjacent to disposal ponds and landfills, maintenance areas, liquid storage tanks, and long term and short term material storage areas. A set of tracking or follow-up procedures shall be used to ensure that appropriate actions are taken in response to the inspections. Records of inspections shall be maintained onsite. Such records are subject to review by the U.S. Environmental Protection Agency, and State, and local agencies with jurisdiction, and must be retained onsite a minimum of 3 years after the date of the inspection.

Note that additional Stormwater Pollution Prevention Plan (SWPPP) requirements for discharges into waters with unavailable parameters or Exceptional Tennessee waters, as described in the subpart 4.6 of this permit may be applicable to your facility.

- 3.2.3.5 Employee Training Employee training programs shall inform personnel responsible for implementing activities identified in the stormwater pollution prevention plan or otherwise responsible for stormwater management at all levels of responsibility of the components and goals of the stormwater pollution prevention plan. Training should address topics such as goals of the pollution prevention plan, spill prevention and control, proper handling procedures for hazardous wastes, good housekeeping and material management practices, and stormwater sampling techniques. The pollution prevention plan shall identify periodic dates for such training, but in all cases training must be held at least annually.
- 3.2.3.6 Recordkeeping and Internal Reporting Procedures A description of incidents (such as spills, or other discharges), along with other information describing the quality and quantity of stormwater discharges shall be included in the plan required under this part. Inspections and maintenance activities shall be documented and records of such activities shall be incorporated into the plan.
- 3.2.3.7 Non-stormwater Discharges
- 3.2.3.7.1 The plan shall include a certification that the discharge has been tested or evaluated for the presence of non-stormwater discharges. The certification shall include the identification of potential significant sources of non-stormwater at the site, a description of the results of any test and/or evaluation for the presence of non-stormwater discharges, the evaluation criteria

or testing method used, the date of any testing and/or evaluation, and the onsite drainage points that were directly observed during the test. Certifications shall be signed in accordance with subpart 7.7 of this permit. Such certification may not be feasible if the facility operating the stormwater discharge associated with industrial activity does not have access to an outfall, manhole, or other point of access to the ultimate conduit which receives the discharge. In such cases, the source identification section of the stormwater pollution prevention plan shall indicate why the certification required by this part was not feasible, along with the identification of potential significant sources of non-stormwater at the site. A discharger that is unable to provide the certification required by this paragraph must notify the Division of Water Resources in accordance with paragraph "Failure to Certify" (below).

- 3.2.3.7.2 Sources of non-stormwater that are combined with stormwater discharges associated with industrial activity must be identified in the plan. The plan shall identify and ensure the implementation of appropriate pollution prevention measures for the non-stormwater component(s) of the discharge. Any non-stormwater discharges that are not authorized under this permit or another NPDES permit should be brought to the attention of the division's local Environmental Field Office (see list of EFOs on page 14).
- 3.2.3.7.3 Failure to Certify Any facility that is unable to provide the certification required (testing for non-stormwater discharges), must notify the Division of Water Resources by not later than 180 days after submitting an NOI to be covered by this permit. If the failure to certify is caused by the inability to perform adequate tests or evaluations, such notification shall describe: the procedure of any test conducted for the presence of non-stormwater discharges; the results of such test or other relevant observations; potential sources of non-stormwater discharges to the storm sewer; and, why adequate tests for such storm sewers were not feasible. Non-stormwater discharges to waters of the state which are not authorized by an NPDES permit are unlawful, and must be terminated.
- 3.2.3.7.4 Sediment and Erosion Control The plan shall identify areas which, due to topography, activities, or other factors, have a high potential for significant soil erosion, and identify structural, vegetative, and/or stabilization measures to be used to limit erosion.
- Management of Runoff The plan shall contain a narrative consideration of the 3.2.3.7.5 appropriateness of traditional stormwater management practices (practices other than those which control the generation or source(s) of pollutants) used to divert, infiltrate, reuse, or otherwise manage stormwater runoff in a manner that reduces pollutants in stormwater discharges from the site. The plan shall provide that measures the permittee determines to be reasonable and appropriate shall be implemented and maintained. The potential of various sources at the facility to contribute pollutants to stormwater discharges associated with industrial activity shall be considered when determining reasonable and appropriate measures. Appropriate measures may include: vegetative swales and practices, reuse of collected stormwater (such as for a process or as an irrigation source), inlet controls (such as snow management activities, oil/water separators), infiltration devices, detention/retention devices, or other equivalent measures.
- 3.2.4 Comprehensive Site Compliance Evaluation. Qualified personnel shall conduct site compliance evaluations at appropriate intervals specified in the SWPPP, but in no case less than once a year. Such evaluations shall provide:

- 3.2.4.1 Areas contributing to a stormwater discharge associated with industrial activity shall be visually inspected for evidence of, or the potential for, pollutants entering the drainage system (and potentially waters of the state). Measures to reduce pollutant loadings shall be evaluated to determine whether they are adequate and properly implemented in accordance with the terms of the permit or whether additional control measures are needed. Structural stormwater management measures, sediment and erosion control measures, and other structural pollution prevention measures identified in the plan shall be observed to ensure that they are operating correctly. A visual evaluation of equipment needed to implement the plan, such as spill response equipment, shall be made.
- 3.2.4.2 Based on the results of the evaluation, the description of potential pollutant sources identified in the plan in accordance with section-Description of Potential Pollutant Sources and pollution prevention measures and controls identified in the plan in section-Measures and Controls shall be revised as appropriate within 2 weeks of such evaluation and shall provide for implementation of any changes to the plan in a timely manner, but in no case more than 12 weeks after the evaluation.
- 3.2.4.3 A report summarizing the scope of the evaluation, personnel making the evaluation, the date(s) of the evaluation, major observations relating to the implementation of the stormwater pollution prevention plan, and actions taken in accordance with the permit shall be made and retained as part of the stormwater pollution prevention plan for at least 3 years from the date of the evaluation. The report shall identify any incidents of noncompliance. Where a report does not identify any incidents of noncompliance, the report shall contain a certification that the facility is in compliance with the stormwater pollution prevention plan and this permit. The report shall be signed in accordance with subpart 7.7 (Signatory Requirements) of this permit.
- 3.2.4.4 Where compliance evaluation schedules overlap with inspections required under 11.O.3.2.4, the compliance evaluation may be conducted in place of one such inspection.

4. Numeric Effluent Limitations

Coal pile runoff is subject to the effluent guidelines described in subpart 5.2 (Coal Pile Runoff) of this permit. The following pollutants of concern shall be monitored at least annually.

Table O-1 Numeric Effluent Limits for Stormwater Discharges from Coal Pile

Pollutant of Concern	Effluent limit
Total Suspended Solids (TSS)	50 mg/L
pН	Between 6.0 and 9.0 S.U.

However, steam electric generating facilities must comply with the requirement of subpart 5.2 (Coal Pile Runoff) immediately upon permit issuance.

5. Monitoring and Reporting Requirements

Permittees subject to Numeric Effluent Limitations described in subpart 5.2 above (Coal Pile Runoff) must submit to the division monitoring results annually on a signed copy of the Discharge Monitoring Report (DMR, see Addendum E).

Permittees subject to Analytical Monitoring Requirements as described in subpart 5.1 of this sector (see below) must submit the benchmark results using an Annual Stormwater Monitoring Report (see Addendum D) to the division.

5.1 Analytical Monitoring Requirements

During the term of this permit, permittees covered under this sector must monitor their stormwater discharges associated with industrial activity at least once per calendar year (annually), except as provided in paragraphs 5.1.3 (Sampling Waiver), 5.1.4 (Representative Discharge), and 5.1.5 (Alternative Certification). For SIC-specific breakdown of monitoring requirements and applicable Monitoring Requirements (listed below), see Table in Part 1 of this industrial sector (1. Discharges Covered Under This Section). Facilities must report in accordance with 5.2(reporting). In addition to the parameter listed in Table O-1 below, the permittee shall maintain a record of the date and duration (in hours) of the storm event(s) sampled; rainfall measurements or estimates (in inches) of the storm event which generated the sampled runoff; the duration between the storm event sampled and the end of the previous measurable (greater than 0.1 inch rainfall) storm event; and an estimate of the total volume (in gallons) of the discharge sampled.

Table O-2. Benchmark Monitoring Requirements for Steam Electric Power Generating Facilities

Pollutant of Concern	Benchmark [mg/L]
Total Recoverable Iron	5

- 5.1.1 Monitoring Periods. Steam electric power generating facilities shall monitor samples collected during any period of a calendar year, as long as the samples are representative of the quantity and quality of the stormwater runoff being discharged from the facility.
- 5.1.2 Sample Type. A minimum of one grab sample shall be taken. All such samples shall be collected from the discharge resulting from a storm event that is greater than 0.1 inches in magnitude and that occurs at least 72 hours from the previously measurable (greater than 0.1 inch rainfall) storm event. The required 72-hour storm event interval is waived where the preceding measurable storm event did not result in a measurable discharge from the facility. The required 72-hour storm event interval may also be waived where the permittee documents that less than a 72-hour interval is representative for local storm events during the season when sampling is being conducted. The grab sample shall be taken during the first 30 minutes of the discharge. If the collection of a grab sample during the first 30 minutes is impracticable, a grab sample can be taken during the first hour of the discharge, and the discharger shall submit with the monitoring report a description of why a grab sample during the first 30 minutes was impracticable. If stormwater discharges associated with industrial activity commingle with process or nonprocess water, then where practicable permittees must

attempt to sample the stormwater discharge before it mixes with the non-stormwater discharge.

5.1.3 Sampling Waiver

- 5.1.3.1 Adverse Conditions When a discharger is unable to collect samples within a specified sampling period due to adverse climatic conditions, the discharger shall collect a substitute sample from a separate qualifying event in the next period and submit the data along with data for the routine sample in that period. Adverse weather conditions which may prohibit the collection of samples include weather conditions that create dangerous conditions for personnel (such as local flooding, high winds, hurricane, tornadoes, electrical storms, etc.) or otherwise make the collection of a sample impracticable (drought, extended frozen conditions, etc.).
- 5.1.3.2 Low Concentration Waiver When the average concentration for a pollutant calculated from monitoring data collected from first 4 calendar years of monitoring is less than the corresponding reporting value for that pollutant (Monitoring Benchmark); a facility may waive monitoring and reporting requirements in the last annual monitoring period. The facility must submit to the Division of Water Resources, in lieu of the monitoring data, a certification that there has not been a significant change in industrial activity or the pollution prevention measures in area of the facility which drains to the outfall for which sampling was waived.
- 5.1.3.3 When a discharger is unable to conduct annual chemical stormwater sampling at an inactive and unstaffed site, the operator of the facility may exercise a waiver of the monitoring requirements as long as the facility remains inactive and unstaffed. The facility must submit to the Division of Water Resources, in lieu of monitoring data, a certification statement on the TMSP Stormwater Monitoring Report stating that the site is inactive and unstaffed so that collecting a sample during a qualifying event is not possible.
- Representative Discharge. When a facility has 2 or more outfalls that, based on a consideration of industrial activity, significant materials, and management practices and activities within the area drained by the outfall, the permittee reasonably believes discharge substantially identical effluents, the permittee may test the effluent of one of such outfalls and report that the quantitative data also applies to the substantially identical outfalls provided that the permittee includes in the stormwater pollution prevention plan a description of the location of the outfalls and explaining in detail why the outfalls are expected to discharge substantially identical effluents. In addition, for each outfall that the permittee believes is representative, an estimate of the size of the drainage area (in square feet) and an estimate of the runoff coefficient of the drainage area (e.g., low (under 40 percent), medium (40 to 65 percent)) or high (above 65 percent)) shall be provided in the plan. The permittee shall include the description of the location of the outfalls, explanation of why outfalls are expected to discharge substantially identical effluents, and estimate of the size of the drainage area and runoff coefficient with the TMSP Stormwater Monitoring Report.
- 5.1.5 Alternative Certification. A discharger is not subject to the monitoring requirements of this section provided the discharger makes a certification for a given outfall, or on a pollutant-by-pollutant basis in lieu of monitoring reports required under paragraph b below, under penalty

of law, signed in accordance with subpart 7.7 (Signatory Requirements), that material handling equipment or activities, raw materials, intermediate products, final products, waste materials, by-products, industrial machinery or operations, significant materials from past industrial activity that are located in areas of the facility within the drainage area of the outfall are not presently exposed to stormwater and are not expected to be exposed to stormwater for the certification period. Such certification must be retained in the stormwater pollution prevention plan, and submitted to the Division of Water Resources in accordance with Part 6.2 of this permit. In the case of certifying that a pollutant is not present, the permittee must submit the certification along with the monitoring reports required under paragraph (b) below. If the permittee cannot certify for an entire period, they must submit the date exposure was eliminated and any monitoring required up until that date. This certification option is not applicable to compliance monitoring requirements associated with effluent limitations.

5.2 Reporting

Permittees with analytical monitoring requirements shall submit monitoring results for each outfall associated with industrial activity [or a certification in accordance with Sections (3), (4), or (5) above] obtained during the annual reporting period on TMSP Stormwater Monitoring Report Form(s). The form(s) shall be submitted 30 days after the sampling results are obtained, but no later than the March 31st of the following calendar year, whichever comes first. For each outfall, one signed TMSP Stormwater Monitoring Report form must be submitted to the Division of Water Resources. Signed copies of TMSP Stormwater Monitoring Reports, or said certifications, shall be submitted to the division at the appropriate EFO for the county where the facility is located. A list of EFOs and their addresses are available in subpart 3.3 above.

- Compliance Monitoring Requirements. Permittees with point sources of coal pile runoff associated with steam electric power generation must monitor these stormwater discharges for the presence of TSS and for pH at least annually (one time per year). Facilities must report in accordance with 5.3.(2) (reporting). In addition to the parameters listed above, the permittee shall maintain a record of the date and duration (in hours) of the storm event(s) sampled; rainfall measurements or estimates (in inches) of the storm event that generated the sampled runoff; the duration between the storm event sampled and the end of the previous measurable (greater than 0.1 inch rainfall) storm event; and an estimate of the total volume (in gallons) of the discharge sampled.
- 5.3.1 Sample Type. A minimum of one grab sample shall be taken. All such samples shall be collected from the discharge resulting from a storm event that is greater than 0.1 inches in magnitude and that occurs at least 72 hours from the previously measurable (greater than 0.1 inch rainfall) storm event. The grab sample shall be taken during the first 30 minutes of the discharge. If the collection of a grab sample during the first 30 minutes is impracticable, a grab sample can be taken during the first hour of the discharge, and the discharger shall submit with the monitoring report a description of why a grab sample during the first 30 minutes was impracticable.

5.3.2 Reporting

Permittees with analytical monitoring requirements shall submit monitoring results for each outfall associated with industrial activity [or a certification in accordance with Sections (3), (4), or (5) above] obtained during the annual reporting period on TMSP Stormwater Monitoring Report Form(s). **The form(s) shall be submitted 30 days after the sampling results are obtained, but no later than the March 31st of the following calendar year, whichever comes first.** For each outfall, one signed TMSP Stormwater Monitoring Report form must be submitted to the Division of Water Resources. Signed copies of TMSP Stormwater Monitoring Reports, or said certifications, shall be submitted to the division at the appropriate EFO for the county where the facility is located. A list of EFOs and their addresses are available in subpart 3.3 above.

- Quarterly Visual Examination of Stormwater Quality. Facilities shall perform and document a visual examination of a stormwater discharge associated with industrial activity from each outfall, except discharges exempted below. The examination must be made at least once in each designated period [described in paragraph (1) below] during daylight hours unless there is insufficient rainfall or snow melt to produce a runoff event.
- 5.4.1 Examinations shall be conducted in each of the following periods for the purposes of visually inspecting stormwater quality associated with stormwater runoff or snow melt: January through March; April through June; July through September; and October through December.
- Examinations shall be made of samples collected within the first 30 minutes (or as soon thereafter as practical, but not to exceed one hour) of when the runoff or snowmelt begins discharging. The examination must be conducted in a well-lit area. No analytical tests are required to be performed on the samples. All such samples shall be collected from the discharge resulting from a storm event that is greater than 0.1 inches in magnitude and that occurs at least 72 hours from the previously measurable (greater than 0.1 inch rainfall) storm event. Where practicable the same individual should carry out the collection and examination of discharges for entire permit term.
- Visual examination reports must be maintained on-site in the pollution prevention plan. The report shall include the examination date and time, examination personnel, the nature of the discharge (i.e., runoff or snow melt), visual quality of the stormwater discharge including observations of color, odor, clarity, floating solids, settled solids, suspended solids, foam, oil sheen, and other obvious indicators of stormwater pollution, and probable sources of any observed stormwater contamination.
- When a facility has two or more outfalls that, based on a consideration of industrial activity, significant materials, and management practices and activities within the area drained by the outfall, the permittee reasonably believes discharge substantially identical effluents, the permittee may collect a sample of effluent of one of such outfalls and report that the examination data also applies to the substantially identical outfalls provided that the permittee includes in the stormwater pollution prevention plan a description of the location of the outfalls and explaining in detail why the outfalls are expected to discharge substantially identical effluents. In addition, for each outfall that the permittee believes is representative, an estimate of the size of the drainage area (in square feet) and an estimate of the runoff coefficient of the drainage area (e.g., low (under 40 percent), medium (40 to 65 percent) or high (above 65 percent)) shall be provided in the plan.

Tennessee Storm Water Multi-Sector General Permit for Industrial Activities (TMSP) Sector O

- When a discharger is unable to collect samples over the course of the visual examination period as a result of adverse climatic conditions, the discharger must document the reason for not performing the visual examination and retain this documentation with the records of the visual examination. Adverse weather conditions which may prohibit the collection of samples include weather conditions that create dangerous conditions for personnel (such as local flooding, high winds, hurricane, tornadoes, electrical storms, etc.) or otherwise make the collection of a sample impracticable (drought, extended frozen conditions, etc.).
- 5.4.6 When a discharger is unable to conduct visual stormwater examinations at an inactive and unstaffed site, the operator of the facility may exercise a waiver of the monitoring requirement as long as the facility remains inactive and unstaffed. The facility must maintain a certification with the pollution prevention plan stating that the site is inactive and unstaffed so that performing visual examinations during a qualifying event is not feasible.